

Project 409: New School Science Block

Client: Fulston Manor School, Sittingbourne, Kent

Construction Details: Aluminium Doors, Double Glazed, Improved Thermal Efficiency, Refurbishment, Safety Glass, School Improvement

[View this case study on WallerServices.com](https://www.wallerservices.com)



New School Science Block

As part of the new science block project, the school required us to remove the old wooden science block. It was well passed its best. The vision was a modern, new school science facility.

The existing building was a 1970s wooden framed and clad structure that had deteriorated over the last 50 years. The school wanted to replace the original building with fit for purpose, bespoke science building. A design team was appointed to create the vision of a new purpose built science lab. The project was submitted to planning and then put out as a open tender opportunity with Waller Building and Glazing being the successful contractor.

Original Building Removal

The first aspect of the new building was to demolish and remove the original 1970s building. Before we started the demolition of the wooded structure, a refurbishment and development survey was carried out. Asbestos was discovered in the original services ducts beneath the building. This had to be removed safely as soon as the building was knocked down. We appointed a registered asbestos removal company to take away and dispose the asbestos containing underground service ducts.

The New Building

The new construction was a traditional build with a strip foundation and a reinforced concrete floor slab. Externally, the building was rendered blockwork with cladding in areas and a tiled roof finish.

Internally, the design of the science block included three science laboratories, a theory classroom and an inventory space. In addition, an entrance lobby, plantroom and a store cupboard were also created.

The specification requirements included the installation of mechanical ventilation, under floor heating, aluminum doors and uPVC double glazed windows throughout. The door and window installation was carried out by our glazing division. This meant that we could keep the cost down as well as continuity throughout the project. Additionally, all gas and electrical works were carried out in accordance with current regulations.

The Final Touches

We worked closely with the school, selecting the science lab layouts, flooring and colour schemes. We procured, assembled and installed all of the lab furniture as well as the fixtures and fittings to the school leadership team's preference.

The final part of the project was landscaping around the new building. This included new pathways, grassed areas and fencing.

The Hand Over

We handed over the building to the school at the end of the project which was completed on time. The school now has a modern and fully complying building which also meets all current energy efficiency standards. The science team were delighted with the new building and couldn't believe what an improvement the bespoke facility was in comparison to the original building.

This new building can now be enjoyed by the students and staff for many years to come.

For more projects similar to this one, please click on the following link- <http://www.wallerservices.com>

Building Services We Provide In Schools

The building services we provide include smaller refurbishments through to extensions and new builds. The services we provide include anything that a school would require. This includes, toilet and kitchen refurbishments. We also install fencing, flooring and carry out complete new builds. Check out our website case studies to view projects that we have recently completed.

Glazing Services We Provide In Schools

In addition to building works, we also carry out works from window and hinge repairs through to complete aluminium and uPVC window and door installations.

Contact Waller Building and Glazing Services

Based in Sittingbourne, we carry out works Kent as well as the south east of England. If you would like a quotation on any size of building or glazing project please contact us. Telephone – 01795 424435. Additionally email mark@wallerservices.com

To check out what we are up to at the moment visit our Facebook page- <https://www.facebook.com/profile.php?id=100063701672876>

As well as this, see what we are tweeting <https://twitter.com/BuildingOnTrust>





Building on trust... together

Waller Associates Ltd

Web: www.wallerservices.com

Tel: 01795 424 435

Fax: 01795 424 812

sales@wallerservices.com